Notification dated 9th January 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M., on 5th February 1936, for constructing a Primary School at Malludihalli, Holalkere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Primary School at Malludihalli, Holalkere Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. For L.S. items current schedule as per actual work will be paid.

Abstract estimate for constructing a Primary School at Malludihalli, Holalkere Taluk.

Sl. No.	Items of work	Unit	Rate	Quantity	Tender rates in	
					Words	Figures
			Rs. a. sp.			
1	Earthwork excavation foundation and filling in basement	C.yd.	0 3 6	72		
2	Stone jelly in chunam concrete	C.ft.	0 4 0	591		
3	Burnt stone in mud	,,	0 3 9	1,679		
4	Burnt brick in mud	,,	0 4 0	2,405		
5	Burnt stone slabs, roughly dressed	S.ft.	0 6 0	161		
6	Chunam plastering	Sqr.	3 4 0	37·85		
7	Whitewashing, two coats	,,	0 4 0	37·85		
8	Teakwood work wrought and put up including wood-oiling	C.ft.	5 0 0	101·25		
9	Flooring with gravel with cow-dung washing	Sqr.	1 0 0	10·25		
10	Roofing with First class Mangalore tiles on teak reepers, etc., complete	,,	33 0 0	18·15		
11	Ridge tiles set in mortar	R.ft.	0 8 0	114		
12	Teakwood door with battened shutters, hinges, bolts, etc., complete	S.ft.	1 4 0	46		
13	Teakwood windows with battened shutters, $\frac{3}{4}$" dia. iron bars, hinges, etc., complete	,,	1 14 0	54		
14	Chunam borders with plastering over gable ends, etc., complete	R.ft.	0 4 0	40		
15	Coping over the compound wall	,,	0 6 0	54		
16	Junglewood gate with iron fittings, etc., complete	L.S.	30 0 0			
10	Chacolate painting, two coats	Sqr.	5 0 0	2·43		
18	Burnt brick in chunam pillar and plastering, etc., complete	Each	6 0 0	6		
19	Constructing gate pillars with brick in chunam, ornamental cap, etc.	,,	8 0 0	2		
20	Cement pointing to basement	Sqr.	4 0 0	3·78		
21	Unforeseen items	L.S.	159 0 0			

H. V. VARADACHARYA,
Executive Engineer.